

SCOPE OF WORK & QUANTUM OF WORK

1. Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade including required key aggregate as specified, spreading coarse aggregate with the help of self propelled / tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy :For 50mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt VG-10 @ 50 kg/10 sqm.
Qty : 5600 Sq Mtr
2. Cutting road and making good the same including supply of extra quantities of materials i.e. aggregate, moorum screening, red bajri and labour required bituminous portion
Qty: 840 Cu Mtr
3. Providing and applying tack coat using hot straight run bitumen of grade VG-10 including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications :On bituminous surface @ 0.50 Kg / sqm.
Qty : 5600 Sq Mtr
4. Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG-10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface including rolling and finishing with road roller all complete.
Qty : 5600 Sq Mtr
5. Providing and laying in position bitumen sand for expansion joint etc using 128 kg bitumen grade VG-10 per cu.m of sand etc. Complete as per direction of Engineer- in- Charge.
Qty : 400 Mtr
6. Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.
Qty : 125 Sq Mtr
7. Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).
Qty: 100 Cu Mtr

8. Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:1.5:3 (1 cement : 1.5 fine sand :3 graded stone aggregate 20 mm nominal size)

Qty: 200 Cu Mtr

9. Random rubble Masonary with hard stone in foundation and plinth in cement concrete 1:6 (stone shall be supplied free of cost at side by the department.

Qty: 72 Cu Mtr

10. Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m for all kinds of soil.

Qty: 48 Cu Mtr